BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019

APPROVED TENDER SCHEDULE –'B'

Item-04

Name of Work:-Providing Temporary Immersion Tank for lord Ganesh Idols at near Yelahanka lake in kempegowda ward no-01

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri RAJESWAREN SATHEESH (SATHYA CONSTRUCTIONS)	
				Rate	Rate In Words
1	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 SR 2018-19	cum	517.50	338.74	Rupees Three Hundred Thirty Eight and Paise Seventy Four Only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19	cum	517.50	91.85	Rupees Ninety One and Paise Eighty Five Only
3	Code 0516-Providing Plastic Sheet (Page No XXIX /Sl No 755 PWD SR 2018-19	Sqm	778.00	6.07	Rupees Six and Paise Seven Only
4	Engaging Unskilled heavy Mazdoor labour for guarding and for helping the public to immersion tank Ganesh idols and to safe guard the public duging the pooja Time (including Expert swimmers)(Page no .LVI)SR 2018-19 sl No 5	days	143.00	468.06	Rupees Four Hundred Sixty Eight and Paise Six Only
5	Supply of water Through water tank for filling Tank	per load	120.00	566.46	Rupees Five Hundred Sixty Six and Paise Forty Six Only
6	Providing stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No 45 Code 400 metal Component PWD SR page No II SR 2018-19	Cum	29.58	1132.92	Rupees One Thousand One Hundred Thirty Two and Paise Ninety Two Only
7	Hire Charges for two Tier Barricading with casurens poles at 2.50mtrs C/C vertically and 1.50 mtrs C/C Horizontaly with Necessary earth work and labour (steel baricading)	Sft	2200.00	10.49	Rupees Ten and Paise Forty Nine Only
8	Hire charge for Armless Plastic Chairs	Nos	1210.00	4.09	Rupees Four and Paise Nine Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri RAJESWAREN SATHEESH (SATHYA CONSTRUCTIONS)	
				Rate	Rate in Words
9	Hire charge for wooden Table of size 6ft x2ft	Nos	220.00	15.74	Rupees Fifteen and Paise Seventy Three Only
10	Hire charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 IIIb)	Mtrs	990.00	9.44	Rupees Nine and Paise Forty Four Only
11	1321 Hire charge of 100 KVA generator including operator, Fuel transportation and Handling charges (PWD SR 2013-14(PXXXX /I.92) code No 132	Hrs	50.00	519.26	Rupees Five Hundred Nineteen and Paise Twenty Five Only
12	Hire Charges for Shamiyana side wall of 8ft hight (Size 15ftx20ft=300sqft)	Rft	720.00	2.10	Rupees Two and Paise Ten Only
13	Hire charge for Shamiyana with Necessary Bambo Poles Erection Charges Including transportation (Size 15ftx20ft=300sqft)	Sft	720.00	5.25	Rupees Five and Paise Twenty Four Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.